APPENDIX B

Air Quality Modeling Protocol



February 15, 2008 Kleinfelder Project No. 91791

Mr. Kevin Schilling
Airshed Dispersion Modeling Coordinator
Idaho Department of Environmental Quality
Air Quality Division
1410 N. Hilton
Boise. ID 83706

SUBJECT: AMBIENT AIR QUALITY MODELING

PROTOCOL for ANDGAR CORPORATION,

BETTENCOURT B-6 DAIRY 3350 SOUTH 2400 EAST JEROME, IDAHO 83338

Dear Mr. Schilling:

Kleinfelder is preparing a Permit to Construct (PTC) application on behalf of the Andgar Corporation for Bettencourt B-6 Dairy located near Jerome, Idaho. The Project includes the installation of an anaerobic digester for processing onsite cow manure and three Genset electrical generators for conversion of the digester biogas to electricity.

The proposed Genset electrical generators will result in criteria pollutant emissions of carbon monoxide, particulate matter, nitrogen oxides, sulfur dioxide and volatile organic compounds.

1 EXECUTIVE SUMMARY

The proposed project will also result in potential emissions of non-carcinogenic toxic air pollutants ("TAPs") listed in IDAPA 58.01.01.585 including acrolein, isomers of xylene, styrene, toluene, and trichloroethylene. The potential emissions of these compounds are not expected to exceed their respective listed TAP screening emission levels ("EL"). In addition, the digester will result in emissions of carcinogenic TAPs listed in IDAPA 58.01.01.586 including acetaldehyde, benzene, dichloromethane, formaldehyde, dichloroethylene, and vinyl chloride. The potential emissions for acetaldehyde and trichloroethylene are not expected to exceed the listed TAP EL, however potential emissions for benzene, dichloromethane, formaldehyde and vinyl chloride may exceed each of there respective TAP EL. Therefore, modeling is expected to be required for these specific TAPs to demonstrate compliance with the Acceptable Ambient Concentration (AAC) or each pollutant.

91791/BOI8R021 Copyright 2008 Kleinfelder February 15, 2008

This ambient air quality modeling protocol ("protocol") is being submitted to the Idaho Department of Environmental Quality Air Quality Division ("IDEQ") for review. The Protocol was prepared consistent with the IDEQ Air Quality Modeling Guidelines ("Guidelines"), revised December 31, 2002, and the associated modeling protocol checklist (see Appendix B). The protocol addresses the approach for assessing the ambient air impacts from the proposed source emissions for comparison with the AAC for TAPs and National Ambient Air Quality Standards (NAAQS) for PM₁₀/PM_{2.5}.

We understand that IDEQ staff will review and approve the modeling protocol. If there are any questions or items of discussion, the following points of contact are available:

Andgar Corporation:

Mr. Kyle Juergens 6920 Salishan Pkwy. A-102 Ferndale, Washington 98248 (360) 366-9900 e-mail: kylej@andgar.com

Kleinfelder:

Mr. Andy Marshall, P.E. 2315 S. Cobalt Point Way Meridian, Idaho 83642 (208) 893-9700 e-mail: amarshall@kleinfelder.com

2 INTRODUCTION AND PURPOSE

2.1. General Overview

Andgar Corporation is proposing to construct an anaerobic digester at Bettencourt B-6 Dairy. Andgar Corporation is constructing the anaerobic digester for Cargill Environmental Finance who in turn is leasing space on the dairy's property. The anaerobic digester is an independent source separate of the dairy.

The facility operates under SIC code 1629. The digester is designed to produce biogas from on-site dairy cattle manure. The resulting biogas will be combusted in three on-site generators that will be used for primary electrical production for the facility and be sold to the local utility. The three generators can operate independently or simultaneously. The electricity will be sold to the local utility. A PTC application will be submitted in support of the permitting for this new air emission source.

Bettencourt B-6 Dairy is a minor source because the potential to emit is less than major source thresholds without requiring limits on its potential to emit.

The facility is located in Gooding County, Idaho which is designated as attainment or unclassifiable for criteria pollutants. The approximate center point of the property is located at UTM 4727165 N by 741792 E, Zone 11. The dairy sits on 1,000 acres and the surrounding area is a sparsely populated, rural area with terrain at about 4,200 feet above mean sea level (MSL). A Site Location Map, Vicinity Map and Facility Layout Map are respectively provided as Figures A-1 through A-3 in Appendix A.

3 EMISSION AND SOURCE DATA

3.1. Facility Processes and Emission Controls Affected

The proposed source will allow for the production of electricity. Since this is Bettencourt B-6 Dairy's initial PTC, existing facility processes or emission controls will not be affected.

3.2. Emission Points and Future Emission Rates

An estimate of the potential emission rates for the proposed source is summarized in Table 3-1. Since this is a new source the current emission rates for all of these pollutants are zero.

Table 3-1: Potential Emission Rates for Genset Generators

Pollutant	PTE	PTE
	(lbs/hr)	(tons/yr)
PM ₁₀	0.17	0.74
SO ₂	9.13	40.0
NO _x	5.65	24.75
CO	12.43	54.45
VOC	5.65	24.75
Acetaldehyde	9.8E-04	4.3E-03
Acrolein	4.4E-04	1.9E-03
Benzene	1.2E-02	5.1E-02
Dichloromethane	1.7E-03	7.4E-03
Formaldehyde	2.9E-02	1.3E-01
Isomers of Xylene	2.3E-03	1.0E-02
Styrene	8.9E-04	3.9E-03
Toluene	4.4E-03	1.9E-02
Trichloroethylene	3.4E-04	1.5E-03
Vinyl Chloride	9.5E-04	4.2E-03

There are three Genset electrical generators proposed to be installed adjacent to each other. The two 750 kW generators have their own 12-inch (0.305 meters) diameter stack extending 20 feet (6.1 meters) above ground. The 330 kW generator has an 8-inch (0.203 meters) diameter stack also extending 20 feet (6.1 meters) above ground. The emissions presented in Table 3-1 represent the total potential emissions if all generators were operating simultaneously at capacity. In an emergency situation the biogas will be flared from the digestor. During a flare event the emission characteristics and potential emission rate will be the same as the emission estimate from the Genset generators.

3.3. Good Engineering Practice (GEP) Stack-height Analysis

The exhaust stack from the genset generators is 20 feet (6.1 meters) in height. Because the stack height is less than 65 meters and is located in simple terrain, the GEP stack-height analysis requires the use of the actual stack height in calculating emission limitations.

3.4. Facility Layout

The facility layout is provided in Figure 3, Appendix A. As shown, the new planned anaerobic digester and biogas electrical generators will be located at the street address 3350 S 2400 E, Jerome, Idaho. The site is southwest of the intersection of W 50 S Road and 2400 E Road. The dairy property includes approximately 1,000 acres. Approximately 1,990 (606 meters) feet east of the emission source is 2400 East Road. This road is the nearest public receptor to the source.

3.5. Source Parameters

The source parameters for the proposed anaerobic digester are summarized in Table 3-2. The Stack Velocity and Stack Temperature are estimates of average operating conditions.

Table 3-2: Source Parameters

Source Description	UTM E	UTM N	Stack Height (m)	Stack Diameter (m)	Stack Velocity (m/sec)	Stack Temp (Deg K)	Receptor Distance (m)
2-Guascor 560 generators	741792	4727165	6.1	0.305	27.8	628	606
1-Guascor 240 generator	741792	4727165	6.1	0.203	28.35	671	606

3.6. Methodology for Including Area and Volume Sources

The new proposed source will be modeled as a point source. Since the proposed generators are the only point source of emissions, no other sources were considered in the modeling analysis. To conservatively assess maximum impacts, each source type will be modeled separately and the maximum source impacts were summed to determine the total maximum impact for the facility. This should provide more conservative modeling results.

3.7. Methodology for Including/Excluding Sources from the Modeling Analysis

We did not include the digestor flares in the modeling analysis. The use of the flares would only occur in an upset condition and the characteristics of the emissions will be the same as the characteristics of the generator emissions. Including the flares will not have any substantial impact on the modeling results.

4 AIR QUALITY MODELING METHODOLOGY

4.1. Model Selection and Justification

The emission rates from the proposed source exceed the modeling thresholds for criteria pollutants requiring ambient air quality modeling for the proposed source. To properly demonstrate compliance with the ambient air quality standards, the SCREEN3 model was chosen to assess the potential air quality impacts from the project. This model was chosen since the facility consists of a simple terrain and simple and isolated emission source. SCREEN3 uses worst case meteorological conditions to estimate worst case emissions.

4.2. Model Setup and Application

The SCREEN3 model was set up following the EPA Guidelines and generally recommended procedures. The modeling options are kept as regulatory default. The inputs included are listed in Table 3-2.

4.3. Land-use Analysis

Following the land—use classification procedure provided in Appendix E of the IDEQ Modeling Guidelines, the area within 3km of the site has been classified as rural. The majority of the 3km radius around the Bettencourt B-6 Dairy is largely agricultural or undeveloped, with the ground cover being mostly wild grasses, weeds and shrubs, and sparsely located trees.

4.4. Building Downwash

The regulatory building downwash option will be used in SCREEN3. The building housing the genset electrical generators has a height of 6.71 meters, a minimum horizontal dimension of 13.7 meters and a maximum horizontal dimension of 30.5 meters.

4.5. Terrain Options

The terrain surrounding Bettencourt Dairy is relatively flat. The surrounding terrain generally is not greater than the stack base elevation. The flat terrain option was selected for the model.

4.6. Choice of Meteorology

The full meteorology option was selected as a worst case scenario for meteorological conditions. This includes all stability classes and wind speeds.

4.7. Discrete Distance Options

The discrete distance option was selected to model to the nearest public receptor. The nearest receptor approximately 1,990 (606 meters) feet east of the emission source is 2400 East Road.

4.8. Background Concentrations

Kleinfelder is proposing to use IDEQ's default background concentrations for rural/agricultural areas presented in Table 4-1.

Table 4-1: Background Concentrations for Criteria Pollutants

Criteria Pollutant	24-hr (ug/m3)	Annual (ug/m3)	1-hr (ug/m3)	8-hr (ug/m3)	3-hr (ug/m3)
PM ₁₀	73	26			
NO ₂	17				
SO ₂	26	8			34
CO			3,600	2,300	

5 APPLICABLE REGULATORY LIMITS

5.1 Methodology for Evaluation of Compliance with Standards

The modeled concentration of criteria pollutants will be compared to the National Ambient Air Quality Standards to demonstrate that the facility impacts will not cause or contribute to an exceedance of the NAAQS. The compliance standards for criteria pollutants are summarized in Table 5-1.

Table 5-1: Applicable Standards for Criteria Pollutants

Criteria Pollutant	NAAQS 24-hr (ug/m3)	NAAQS Annual (ug/m3)	NAAQS 1-hr (ug/m3)	NAAQS 8-hr (ug/m3)	NAAQS 3-hr (ug/m3)
Total PM					
PM ₁₀	150				
PM _{2.5}	35	15			
NO ₂		100			
SO ₂	365	80			1,300
CO			40,000	10,000	
Lead					

SCREEN3 produces output for a one-hour average only. This one-hour average concentration must be adjusted to estimate the concentration for the appropriate averaging period. The one-hour average model output will be converted to averaging periods consistent with the standard for the pollutant modeled through the use of persistence factors presented in Table 5-2.

Table 5-2: Persistency Conversion Factors for SCREEN3

Averaging Period	Simple Terrain Conversion Factor
3- hour	0.9
8-hour	0.7
24-hour	0.4
Quarterly	0.13
Annual (Criteria)	0.8
Annual (Carcinogenic TAPs)	0.125

The modeled concentrations of the TAP emissions will be compared to their respective Acceptable Ambient Concentrations presented in IDAPA 58.01.01 Sections 585 and 586. The compliance standards for TAP emissions are summarized in Table 5-2.

Table 5-3: Applicable Standards for TAPs

ТАР	AAC (ug/m3) 24-hr Avg	AACC (ug/m3) Annual Avg
Acetaldehyde		0.45
Acrolein	12.50	
Benzene		0.12
Dichloromethane		0.24
Formaldehyde		0.077
Isomers of Xylene	21,750	
Styrene	1,000	
Toluene	18,750	
Trichloroethylene	13,450	0.77
Vinyl Chloride		0.14

5.2 Preliminary Analysis

The proposed project will also result in potential emissions of non-carcinogenic toxic air pollutants ("TAPs") listed in IDAPA 58.01.01.585 including acrolein, isomers of xylene, styrene, toluene, and trichloroethylene. The potential emissions of these compounds are not expected to exceed their respective listed TAP screening emission levels ("EL"). In addition, the digester will result in emissions of carcinogenic TAPs listed in IDAPA 58.01.01.586 including acetaldehyde, benzene, dichloromethane, formaldehyde, dichloroethylene, and vinyl chloride. The potential emissions for acetaldehyde and trichloroethylene are not expected to exceed the listed TAP EL, however potential emissions for benzene, dichloromethane, formaldehyde and vinyl chloride may exceed each of there respective TAP EL. Therefore, modeling is expected to be required for these specific TAPs to demonstrate compliance with the Acceptable Ambient Concentration (AAC) or each pollutant.

5.3 Full Impact Analysis

The full impact analysis will include an evaluation of the modeled impacts to Ambient air quality. If the maximum modeled concentrations exceed significant contribution levels. The modeled impacts will be added to the respective background concentration for each pollutant.

5.4 Presentation of Results

The results of the air quality modeling will be included in detailed report as an appendix to the Permit to Construct application submitted for the project. A summary of the results will be included in the PTC application. We will follow the State of Idaho Air Quality Modeling Guidelines dated December 31, 2002.

The report will include a detailed description of the source and the potential emissions, modeling methods and results. The results will be presented in a tabular format for The permit application will include easy comparison to the regulatory limits. documentation and justification for the engineering parameters used in the modeling analysis and calculations presenting how stack gas parameters were estimated.

If you have any questions, please contact the undersigned at (208) 893-9700.

Sincerely,

KLEINFELDER

Kelli Wetzel Air Oran

Andrew Marshall, P.E.

Environmental Department Manager

Attachments:

References

Figures

Site Location Map Figure 1:


Figure 2: Vicinity Map


Facility Layout Detail Figure 3:

Modeling Protocol Checklist

REFERENCES

- EPA, 2000. *Meteorological Monitoring Guidance for Regulatory Modeling Applications*. EPA Publication No. EPA-454/R-99-005. U.S. Environmental Protection Agency, Research Triangle Park, NC.
- EPA, 1995. SCREEN3 Model User's Guide. U.S. Environmental Protection Agency, Research Triangle Park, NC.
- EPA's SCRAM Web site: http://www.epa.gov/scram001/index.htm.
- IDAPA 58.01.01, et seq. Rules for the Control of Air Pollution in Idaho.
- IDEQ, 2002. State of Idaho Air Quality Modeling Guideline, Doc. IDAQ-011 (rev. 1 12/31/02).








Table A-1

Modeling Protocol Checklist for New Minor Sources or Minor Modifications

Modeling Protocol Checklist for New Minor Sources or Minor Modifications					
Checklist Item	Completed	Protocol Section			
	(yes / no)				
Introduction and Purpose	Yes	2			
 General overview, facility description, terrain description 	Yes	2.1			
Project Overview	Yes	2.1			
 Goals of the air quality impact analysis (i.e., demonstrate compliance for a permit to construct or a Tier II operating permit) 	Yes	2.1			
Applicable regulations and requirements	Yes	Exec Summary			
Pollutants of concern	Yes	Exec Summary			
Emission and Source Data	Yes	3			
Facility processes and emission controls effected by the permitting action	Yes	3.1			
Include a list of emission points that will be included in the application. Present a table showing current actual and future allowable emission rates (in maximum pounds per hour tons per year) and the requested emission increase (future allowable minus current actual)	Yes	3.2			
Good engineering practice (GEP) stack-height analysis	Yes	3.3			
Facility layout: location of sources, buildings, and fence lines	Yes	3.4			
Source parameters (emissions rates, UTM coordinates, stack height, stack elevation, stack diameter, stack-gas exit velocity, and stack-gas exit temperature) for each new or modified emission point	Yes	3.5			
Methodology for including area and volume sources in the modeling analysis	Yes	3.6			
Methodology for including/excluding sources from the modeling analysis	Yes	3.7			
Air Quality Modeling Methodology	Yes	4			
Model selection and justification	Yes	4.1			
Model setup and application Model options (i.e., regulatory default) Terrain Options Land-use analysis Building Downwash Choice of Meteorology Discrete Distance Option	Yes	4.2			
Elevation data Methodology for accounting for complex terrain	n/a				

Table A-1 (Continued) Modeling Protocol Checklist for New Minor Sources or Minor Modifications

Checklist Item	Completed (yes / no)	Protocol Section
 Receptor network Description of receptor grids – include methodology for ensuring the maximum concentration will be estimated Discussion/justification of ambient air Determination of receptor elevations 	n/a	
 Meteorological data Selection of meteorological databases – justification of appropriateness of meteorological data to area of interest Meteorological data processing Meteorological data analysis (e.g., wind rose) 	Yes	4.6
Background concentrations	n/a	
Applicable Regulatory Limits	Yes	5
Methodology for evaluation of compliance with standards (i.e., determination of design concentration)	Yes	5.1
Full impact analysis TAPs analysis NAAQS analysis	Yes	5.1
Presentation of results – state how the results of the modeling analysis will be displayed (i.e., list what information will be included)	Yes	5.1
References	Yes	6

APPENDIX C

Modeling Protocol Approval Letter



1410 NORTH HILTON, BOISE, ID 83706 · (208) 373-0502

C. L. "BUTCH" OTTER, GOVERNOR TONI HARDESTY, DIRECTOR

February 29, 2008

Kelli Wetzel Kleinfelder Boise, Idaho

RE: Modeling Protocol for an Anaerobic Digester and Generators at Bettencourt B-6 Dairy in Gooding County, Idaho

Kelli:

DEQ received your dispersion modeling protocol on February 15, 2008. The modeling protocol was submitted on behalf of Andgar Corporporation (Andgar) for Bettencourt B-6 Dairy (Bettencourt). The modeling protocol proposes methods and data for use in the ambient impact analyses of a Permit to Construct application for construction of an anaerobic digester and three electrical generators to be located on property leased from Bettencourt in Gooding County, Idaho.

The modeling protocol has been reviewed and DEQ has the following comments:

• <u>Comment 1: Facility Definition and Ambient Air Boundary.</u> The protocol asserts the digester and generators will be a separate facility from the Bettencourt Dairy, and that Cargill Environmental Finance will be leasing space on Bettencourt's property. If these are separate facilities, then the ambient air boundary will be the boundary of the leased property rather than the property boundary of the dairy.

A good test to evaluate whether it should be one or two facilities with regard to ambient air is to examine how exposures to emissions would be legally handled. If a single occupational health and safety program would have authority and responsibility for employees of both the dairy and the digester facility, then both facilities could be considered as one for the purpose of establishing the ambient air boundary.

- <u>Comment 2: Use of SCREEN3.</u> The use of SCREEN3 is approvable for this project provided the following are met:
 - 1. Each generator is modeled at emissions associated with maximum allowable operations, and the maximum 1-hour concentration for each generator is recorded. The total impact is the sum of maximum modeled concentrations determined for each of the three generators.
 - 2. Building dimensions used for downwash must be those associated with the worst-case building. The governing building is that building the results in the

highest GEP stack height calculation. The GEP height is given by H=S+1.5L, where S= the height of the building and L= the lesser dimension of either the height or projected width. Any emissions stack with a distance of 5L may cause plume downwash and should be evaluated.

Comment 3: Documentation and Verification of Stack Parameters. The application should provide documentation and justification for stack parameters used in the modeling analyses, clearly showing how stack gas temperatures and flow rates were estimated. In most instances, applicants should use typical parameters, not maximum temperatures and flow rates. If the application does not clearly indicate how values for parameters were measured or calculated, the application will be determined incomplete.

DEQ's modeling staff considers the submitted dispersion modeling protocol, with resolution of the additional items noted above, to be approved. It should be noted, however, that the approval of this modeling protocol is not meant to imply approval of a completed dispersion modeling analysis. Please refer to the *State of Idaho Air Quality Modeling Guideline*, which is available on the Internet at http://www.deq.state.id.us/air/permits_forms/permitting/modeling_guideline.pdf, for further guidance.

To ensure a complete and timely review of the final analysis, our modeling staff requests that copies of all modeling input and output files are submitted with an analysis report. If you have any further questions or comments, please contact me at (208) 373-0112.

Sincerely,

Kewin Schilling

Kevin Schilling Stationary Source Air Modeling Coordinator Idaho Department of Environmental Quality 208 373-0112

APPENDIX D

Emissions Calculations and Screen3 Output

Emission Calculations Bettencourt B-6 Dairy, Jerome, Idaho Three 750 kW Genset Electrical Generators (Guascor 560)

Capacity Assumptions					
Power	3,171	bhp			
Fuel consumption	6,570	btu/bhp-hour			
Fuel input at capacity 20.8 MMBtu/hr					

lbs/hr \times 0.126 = g/sec

	Emission			Emissions	
Pollutant	factor (lb/MMbtu)	Data Source	lbs/hr	tons/yr	grams/sec
PM10	9.99E-03	AP-42 Section 3.2, Table 3.2-2 (includes filterable and	0.21	0.91	2.6E-02
PM2.5	9.99E-03	condensible)	0.21	0.91	2.6E-02
SO2	6.69E-01	Vendor	13.9	61.0	1.8E+00
NOx	3.36E-01	Vendor	7.0	30.6	8.8E-01
CO	7,38E-01	Vendor	15.4	67.4	1.9E+00
VOC	3.36E-01	Vendor	7.0	30,6	8.8E-01
Lead	nd	Vendor			0.0E+00
Acetaidehyde	5.30E-03	EPA AP-42 Section 3.1, April 2000 (Rating D)	1.1E-01	4.8E-01	1.4E-02
Acrolein	2.60E-05	JMM cons eng. Dec 10, 1990 - Fire database (Rating U)	5.4E-04	2.4E-03	6.8E-05
Benzene	6.90E-04	Radian fire database 1993 release (Rating U)	1.4E-02	6.3E-02	1.8E-03
Dichloromethane	1.01E-04	Radian fire database 1993 release (Rating U)	2.1E-03	9.2E-03	2.6E-04
Formaldehyde	1.90E-04	EPA AP-42 Section 3.1, April 2000 (Rating D)	4.0E-03	1.7E-02	5.0E-04
Isomers of Xylene	1.37E-04	Radian fire database 1993 release (Rating U)	2.9E-03	1.2E-02	3.6E-04
Nickel	2.00E-06	EPA AP-42 Section 3.1, April 2000 (Rating D)	4.2E-05	1.8E-04	5.2E-06
Selenium	1.10E-05	EPA AP-42 Section 3.1, April 2000 (Rating D)	2.3E-04	1.0E-03	2.9E-05
Styrene	5.26E-05	Radian fire database 1993 release (Rating U)	1.1E-03	4.8E-03	1.4E-04
Toluene	2.62E-04	Radian fire database 1993 release (Rating U)	5.5E-03	2.4E-02	6.9E-04
Trichloroethylene	2.00E-05	JMM cons eng. Dec 10, 1990 - Fire database (Rating U)	4.2E-04	1.8E-03	5.2E-05
Vinyl Chloride	5.60E-05	JMM cons eng. Dec 10, 1990 - Fire database (Rating U)	1.2E-03	5.1E-03	1.5E-04

Total Emissions Compared to TAP Screening Els

		Emissions		TAP Scr	eening
			1	TAP	
				Screening	Exceeds
Pollutant	lbs/hr	tons/yr	grams/sec	EL (lb/hr)	EL?
PM10	0.21	0.91	2.6E-02		
PM2.5	0.21	0.91	2.6E-02		
SO2	13.93	61.03	1.8E+00		
NOx	6.99	30.62	8.8E-01	Not app	licable
co	15.38	67.36	1.9E+00		
VOC	6.99	30.62	8.8E-01		
Lead					
Acetaldehyde	1.1E-01	4.8E-01	1.4E-02	3.0E-03	Yes
Acrolein	5.4E-04	2,4E-03	6.8E-05	1.7E-02	No
Benzene	1.4E-02	6,3E-02	1.8E-03	8.0E-04	Yes
Dichloromethane	2.1E-03	9.2E-03	2.6E-04	1.6E-03	
Formaldehyde	4.0E-03	1.7E-02	5.0E-04	5.1E-04	Yes
Isomers of Xylene	2.9E-03	1.2E-02	3.6E-04	2.9E+01	No
Nickel	4.2E-05	1.8E-04	5.2E-06	2.7E-05	Yes
Selenium	2.3E-04	1.0E-03	2.9E-05	1.3E-02	No
Styrene	1.1E-03	4.8E-03	1.4E-04	6.7E+00	
Toluene	5.5E-03	2.4E-02	6.9E-04	2.5E+01	No
Trichloroethylene	4.2E-04	1.8E-03	5.2E-05	5.1E-04	
Vinyl Chloride	1.2E-03	5.1E-03	1.5E-04	9.4E-04	Yes

Emission Factor Calculation Details

Refer to Stoichiometric conversion of H2S to SO2 following worksheet

1 gr/ bhp-hour / 453.59 gr/lb / 6,570 BTU/bhp-hour = 3.36E-07 lb/BTU
2.2 gr/ bhp-hour / 453.59 gr/lb / 6,570 BTU/bhp-hour = 7.38E-07 lb/BTU
1 gr/ bhp-hour / 453.59 gr/lb / 6,570 BTU/bhp-hour = 3.36E-07 lb/BTU

Ambient Air Quality Analysis (Page 1) Bettencourt B-6 Dairy, Jerome, Idaho

Persistency Factors			
3 hour	0.9		
8 hour	0.7		
24 hour	0.4		
Annual criteria	0.08		
Annual TAPs	0.125		

Maximum SCREEN3 Impact using <u>concentration</u> input of 1 gram/sec (X/Q):

Model Results 476.00 (ug/m3)/(g/s)

Three 750 kW Genset Electrical Generators (Guascor 560)

Pollutant	Emissions (grams/sec)	Estimated impacts (ug/m3) (1-hr avg)	1-hr average adjusted to 24 hr average	1 -hr average adjusted to annual average	1-hr average adjusted to 8 hr average	1-hr average adjusted to 3 hr average
PM10	2.62E-02	1.25E+01	4.99E+00	9.98E-01		
PM2.5	2.62E-02	1.25E+01	4.99E+00	9.98E-01		
SO2	1,76E+00	8.36E+02	3.34E+02	6.69E+01		7.52E+02
NO2 (Note 1)	6.61E-01	3.14E+02		2.52E+01		
co	1.94E+00	9.22E+02			6.46E+02	
voc	8.81E-01	Modeling not conducted				
Lead	0.00E+00	0.00E+00		:		
Acetaldehyde	1.39E-02	Emissions are below EL				
Acrolein	6.82E-05		Emissions are below EL			
Benzene	1.81E-03	8.62E-01		1.08E-01		
Dichloromethane	2.65E-04	1.26E-01		1.57E-02		
Formaldehyde	4.99E-04	2.37E-01		2.97E-02		
Isomers of Xylene	3,59E-04			Emissions are below	EL	
Nickel	5.25E-06	2.50E-03		3.12E-04		
Selenium	2.89E-05					
Styrene	1.38E-04			Emissions are below	r EL	
Toluene	6.88E-04	Emissions are below EL.				
Trichloroethylene	5,25E-05	Emissions are below EL				
Vinyl Chloride	1.47E-04		1	8.75E-03		

NOx conversion to NO2 assumed 0.75, per EPA guidance.

Ambient Air Quality Analysis (Page 2) Bettencourt B-6 Dairy, Jerome, Idaho

DEQ Background Concentrations For Rural Areas

	Pollutant	Background Concentration (ug/m3)
PM10	24 hour	73
	Annual	26
SO2	3 hour	34
	24 hour	26
	Annual	8
NO2	Annual	17
co	1 hour	3,600
	8 hour	2,300

Estimated Impacts Including Background Concentrations

	ollutant	Modeled Impact (ug/m3)
PM10	24 hour	78
	Annual	27
SO2	3 hour	786
	24 hour	360
	Annual	75
NO2	Annual	42
CO	1 hour	4,522 2,946
	8 hour	2,946

Pollutant	Averaging Period	Modeled Impacts (µg/m³) (Note 1)	NAAQS or AAC (μg/m³)	
	24 hour	77.99	150	
PM ₁₀	Annual	27.00	50	
	24 hour		35	
PM _{2.5}	Annual	Note 2	15	
NO₂	Annual	42.16	100	
	3 hour	786.09	1,300	
]	24 hour	360.26	365	
SO ₂	Annual	74.85	80	
	1 hour	4,522.40	40,000	
со	8 hour	2,945.68	10,000	
Acetaldehyde	Annual	Below TAP EL		
Acrolein	24 hour	Below TAP EL		
Benzene	Annual	0.11	0.12	
Dichloromethane	Annual	0.02	0.24	
Formaldehyde	Annual	0.03	0.08	
Isomers of Xylene	24 hour	Below	OW TAP EL	
Nickel	Annual	0.00031	0.004	
Selenium	24 hour	Below TAP EL		
Styrene	24 hour	Below TAP EL		
Toluene	24 hour	Below TAP EL		
Trichloroethylene	24 hour Annual	Below	TAP ELs	
Vinyl Chloride	Annual	0.01	0.14	

Note 1 – Modeled Impacts for primary pollutants considers background concentrations.

Note 2 – Background for PM2.5 has not been established and modeled impacts could not be determined

H2S top SO2 Conversion Bettencourt B-6 Dairy, Jerome, Idaho

Assumptions:

2,400 ppm SO2 concentration 379 scf gas/lb-mole

34 Molecular weight of H2S

64 Molecular weight of SO2 9.55 scf/sec exhaust rate

825120

Emission Factor

```
12:46:51
     SCREEN3 MODEL RUN ***
 *** VERSION DATED 96043 ***
C:\Lakes\ScreenView\dcd.scr
SIMPLE TERRAIN INPUTS:
                                      POINT
   SOURCE TYPE
                                    1.00000
   EMISSION RATE (G/S)
   STACK HEIGHT (M)
                                     7.9300
   STK INSIDE DIAM (M)
                                       .2540
   STK EXIT VELOCITY (M/S)=
STK GAS EXIT TEMP (K) =
                                    40.0000
                                   628.1500
   AMBIENT AIR TEMP (K)
                                   293.0000
                            =
   RECEPTOR HEIGHT (M)
                                      1.5000
                                      RURAL
   URBAN/RURAL OPTION
                                      6.7100
   BUILDING HEIGHT (M)
   MIN HORIZ BLDG DIM (M)
                                    13.7000
   MAX HORIZ BLDG DIM (M)
                                    30.5000
THE REGULATORY (DEFAULT) MIXING HEIGHT OPTION WAS SELECTED. THE REGULATORY (DEFAULT) ANEMOMETER HEIGHT OF 10.0 METERS WAS ENTERED.
                  3.376 M**4/S**3;
                                     MOM. FLUX =
                                                     12.037 M**4/S**2.
BUOY. FLUX =
*** FULL METEOROLOGY ***
**********
*** SCREEN DISCRETE DISTANCES ***
*********
                            O. M ABOVE STACK BASE USED FOR FOLLOWING DISTANCES ***
*** TERRAIN HEIGHT OF
                                                                SIGMA
                                                                         SIGMA
                               U10M
                                       USTK
                                             MIX HT
                                                       PLUME
  DIST
            CONC
                                                                                 DWASH
                                                                         z (M)
          (UG/M**3)
                                      (M/S)
                                               (M)
                                                      HT (M)
                                                                Y(M)
                       STAB
                              (M/S)
   (M)
                                                                          3.50
                               10.0
                                       10.0
                                             3200.0
                                                        8.00
                                                                 1.95
                                                                                   SS
    21.
                         4
           476.0
           MEANS NO CALC MADE (CONC = 0.0)
 DWASH=NO MEANS NO BUILDING DOWNWASH USED
 DWASH=HS MEANS HUBER-SNYDER DOWNWASH USED
 DWASH=SS MEANS SCHULMAN-SCIRE DOWNWASH USED
 DWASH=NA MEANS DOWNWASH NOT APPLICABLE, X<3*LB
**********************
    *** REGULATORY (Default) ***
PERFORMING CAVITY CALCULATIONS
  WITH ORIGINAL SCREEN CAVITY MODEL
(BRODE, 1988)
                                          *** CAVITY CALCULATION - 2 ***
 *** CAVITY CALCULATION - 1 ***
                                           CONC (UG/M**3)
                                                                      .0000
  CONC (UG/M**3)
                             .0000
                                           CRIT WS @10M (M/S) = CRIT WS @ HS (M/S) =
  CRIT WS @10M (M/S) = CRIT WS @ HS (M/S) =
                             99.99
                                                                      99.99
                                                                      99.99
                             99.99
                                           DILUTION WS (M/S)
                                                                      99.99
  DILUTION WS (M/S)
                             99.99
  CAVITY HT (M)
CAVITY LENGTH (M)
ALONGWIND DIM (M)
                                           CAVITY HT (M)
                                                                       6.74
                              7.47
                       =
                                           CAVITY LENGTH (M)
                                                                      15.87
```

Page 1

ALONGWIND DIM (M)

=

30.50

24.98

13.70

=

 $10\ diam\ 40\ ms\ 70\ foot\ receptor$ CAVITY CONC NOT CALCULATED FOR CRIT WS > 20.0 M/s. CONC SET = 0.0

CALCULATION PROCEDURE	MAX CONC (UG/M**3)	DIST TO MAX (M)	TERRAIN HT (M)
SIMPLE TERRAIN	476.0	21.	0.

APPENDIX E

Affidavit of Publication – Public Notice Meeting

Affidavit of Publication STATE OF IDAHO) COUNTY OF TWIN FALLS) SS.

I, Ruby Aufderheide, being first duly sworn upon oath, depose and say that I am Legal Clerk of the TIMES-NEWS, published daily at, Twins Falls, Idaho, and do solemnly swear that a copy of the notice of advertisement, as per clipping attached, was published in the regular and entire issue of said newspaper, and not in any supplement thereof, for one consecutive publication, commencing with the issue dated 25th day of March, 2008 and ending with the issue dated 25th day of March, 2008

And I do further certify that said newspaper is a consolidation, effective February 16, 1942, of the Idaho Evening Times, published theretofore daily except Sunday, and the Twin Falls News, published theretofore daily except Monday, both of which newspapers prior to consolidation had been published under said names in said city and county continuously and uninterruptedly during a period of more than twelve consecutive months, and said TIMES-NEWS, since such consolidation, has been published as a daily newspaper except Saturday, until July 31, 1978, at which time said newspaper began daily publication under said name in said city and county continuously and uninterrupted.

And I further certify that pursuant to Section 60-108 Idaho Code, Thursday of each week has been designated as the day on which legal notice by law or by order of any court of competent jurisdiction within the state of Idaho to be issued thereof Thursday is amounced as the day on which said legal will be published.

STATE OF IDAHO COUNTY OF TWIN FALLS

On this 25th day of March, 2008, before me,

> Notary Public for Idaho Residing at Twin Falls, Idaho.

My commision expires:

5-19-09

PUBLIC NOTICE

Gargill Environmental Finance has applied for an air quality permit to construct for an anaerobio digester located at 3350 South 2400 East in Jerome, ID. An informational meeting will be held in Jerome Public Library's Side B Conference Room located at 100 1st Avenue East, Jerome, ID at 5:30pm on April 8, 2008.

PUBLISH: March 25, 2008

LINDA CAPPS-McGUIRE NOTARY PUBLIC STATE OF IDAHO

APPENDIX F

EPA letter regarding 40 CFR 60, Subpart JJJJ

From: Narvaez.Madonna@epamail.epa.gov [mailto:Narvaez.Madonna@epamail.epa.gov]

Sent: Tue 2/12/2008 10:53 AM

To: Kyle Juergens

Subject: RE: another question

Hi, Kyle. I heard back from the rule writer, Jaime Pagan:

"What the section is saying is that, in the cases where 3-way catalysts are used to meet the standards, an air-to-fuel ratio controller is expected. The 3-way catalysts work only with rich-burn engines. Lean-burn engines can meet the standards without catalysts so paragraph (g) really doesn't apply to them."

So it doesn't apply to your case.

narvaez.madonna@epa.gov

Madonna Narvaez Region 10 Air Toxics Team Leader USEPA Region 10 1200 Sixth Avenue, Ste. 900, MC: AWT-107 Seattle, WA 98101-3140 (206) 553-2117 fax: (206) 553-0110